

AUG 22 1995

COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 MAR 23 PM 4 09

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in PAVILION TWP.

KALAMAZOO
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 3 S R 10 W B-3
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Section S T R

James [Signature]
CLERK-REGISTER

1 PG 1281

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3	●											
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Allen H. McMachen field survey on January 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - R. Clark, D.S., Set Quarter Section Post
W. Oak 16" S. 32° E. 69 lks.
Hickory 13" N. 16° W. 13 lks.

1888 - F. Hodgeman, C.S., Found marked Stone at intersection of roads,
Set Post, B. Walnut 6" N. 11½° W. 49 lks.
Maple 4" S. 48½° W. 68 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile 1.8' below surface in monument box (box at surface).

RAIIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

2/16/95
R. [Signature]



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison monument over existing Tile in existing monument box. Accessories:

- Nail & Tab in E. Face 6" Maple N. 05° W. 33.60'
- Nail & Tab in E. Face 24" Maple S. 15° W. 238.90'
- Nail & Tab in S.E. Face Power Pole S. 55° W. 242.65'
- Nail & Tab in S.W. Face Power Pole N. 70° W. 101.68'

Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 3/22/95