

**SURVEY & REMONUMENTATION**

SEP 14 1998

LIBER PAGE 286

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Pavilion Twp.  
Kalamazoo (County)

Located In:

Corner Code #

1. Public Land Survey	T	3S.	R	10W.	B-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
1998 FEB 5 PM 3 49  
Clerk - Register  
*Janice Johnson*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5	18	17	16	15	14	13						
6												
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on November 10, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1827 - Robert Clark, D.S., Set quarter Section post, W. Oak 13" N. 36° E. 36 lks. W. Oak 24" S. 17° W. 14 lks.

1870 - F. Hodgman, C.S., "Quarter post said by Smith to have been kept in place of original set by Watson, County Surveyor. Stakes planted when witnesses were good."

1888 - F. Hodgman, C.S., "Found stone which Elijah Smith says he put in place of the original stake which he has kept up for 53 years. He says the stone is 3' long & 2' square at the base. Sycamore 18" N. 74° E. 117 lks., Maple 12" S. 21° E. 119 lks.."

1865 - F. Stimson, C.S., "Found stake said by A.H. Smith & E.S. Smith to have been kept in place of original stake. Trees & stumps gone."

1872 - S. Hodgman, D.C.S., "Found stake"

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found drilled stone per (2) 1888 witnesses. Drill hole had large iron bolt in it.

**RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP**  
*12/10/97 R.E.S.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found stone is accepted a careful and faithful perpetuation of the position of the original corner. Broke off top 2" and placed 6" of Harrison Monument over drill hole (in concrete), placed monument box over., Accessories:

- Nail (existing) in U. Pole N. 50° W. 67.3'
- Nail (existing) in 24" Maple S. 40° W. 61.30'
- "PK" Nail (existing) in 42" Sycamore (1888 Hodgman) N. 75° E. 77.3'
- Nail (existing) in 32" Maple (1888 Hodgman) S. 20° E. 79.40'



Signed by *Allen H. McMachen* Date 1/19/98  
Surveyor's Michigan License No. 16935