

**SURVEY &  
REMONUMENTATION**

1  
2  
APR 27 1995  
COMMISSION

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 '94 DEC 15 PM 1 36

For corners in Pavilion Twp.

<u>Kalamazoo</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>10W</u>	<u>B-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*[Signature]*  
CLERK-REGISTER

LIBER 1 PG 1215

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Allen McMachen, in a field survey on March 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1880's - F. Hodgeman C.S. placed Clay Tile Post during official Township Remonumentation.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
6												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found broken Clay Tile 1' below surface, removed broken section and found bottom section of Tile.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
5/18/94  
*[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Found Clay Tile is accepted as a careful and faithful perpetuation of the original corner. Placed Harrison Monument over existing bottom section of Tile and Monument box, Accessories:

- "PK" Nail & Tab in S.E. side Power Pole N. 30° E. 22.33'
- 3/4" Iron Rod N. 75° E. 4.82'
- Nail & Tab in N. side 16" Maple S. 54° W. 53.51'
- Nail & Tab in S. side 14" Cherry N. 88° W. 41.82'

Signed by Allen H. McMachen Date 11/17/94  
Surveyor's Michigan License No. 16935