

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 432

For corners in Pavilion Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>10W</u>	<u>B-10</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '98 DEC 29 AM 11 26
 J. J. [Signature]
 CLERK - REGISTER
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert E. Snell, in a field survey on April 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors.
 1907: E. Strong, County Surveyor; shows center 1/4 post but does not describe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1928: Glen Wheaton, County Surveyor; found stake, stones and iron in marsh in East and West fence, 20' East of fence South.
 1998: Found 1" pinch pipe in stones. The stones are 6" to 10" in diameter and in several layers.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 12-17-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B=10: Center 1/4 post, Section 30, T. 3 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 17, 1998 and is accepted as the best available evidence of the position of the corner. Found 1" pinch pipe in several layers of stone, as found in 1928 survey by Glen Wheaton, County Surveyor. Placed 30" Harrison over 1" pinch pipe.

PK Nail in South Side	14" Oak	N. 40° W.	7.95'
PK Nail in East Side	14" Oak	S. 20° W.	24.25'
PK Nail in East Side	6" Maple	N. 05° E.	41.80'
PK Nail in South Side	16" Oak	East	18.10'

Signed by Robert E. Snell
 Surveyor's Michigan License No. 9734

Date 12-29-98