

AUG 22 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

95 MAR 23 PM 4 09

For corners in PAVILION TWP.

KALAMAZOO
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 3 S R 10 W C-5
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

James [Signature]

CLERK-REGISTER

LIBER 1 PG 1282

Register of Deeds Stamp & File Number

I, Allen H. McMachen a field survey on January 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - R. Clark, D.S., Set Post
Pepperidge 12" WEST 339 lks.
R. Oak 14" EAST 151 lks.
- 1872 - S. Hodgeman, D.L.S., Sec. Cor. stake & stones in causeway.
- 1888 - F. Hodgeman, C.S., Found stake and stone in causeway, Set Post
B. Ash 2" N. 3 1/2° W. 48 1/2 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile 0.8' below surface in monument box (box at surface).

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

2/16/95 *R.E.S.*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed standard sleeve over existing Tile in existing monument box. Accessories:

- Nail & Tab in S. Face 24" Maple N. 75° W. 104.88'
- Nail & Tab in S.W. Face 18" Ash N. 25° W. 53.65'
- Nail & Tab in N.W. Face 16" Ash N. 55° E. 54.45'
- Nail & Tab in E. Face 22" Ash S. 05° E. 23.75'

Signed by Allen H. McMachen

Date 3/22/95

Surveyor's Michigan License No. 16935