

**SURVEY &
REMONUMENTATION**

1
2

OCT 06 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Pavilion Twp.
Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>3S.</u>	R	<u>10W.</u>	<u>C-6</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		

LIBER
CLERK - REGISTER
Jennifer Brown

PAGE 177
97 JUL 29 PM 3 57
STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on June 18, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - Robert Clark, D.S., Set quarter Section post, Y. Oak 30" S. 05° E. 140 lks. W. Oak 16" N. 50½° E. 61 lks.

1888 - F. Hodgman, C.S., Stone of resurvey and bearing tree S.W. in place, set post. W. Oak 8" S. 6½° W. 21½ lks.

1870 - F. Hodgman, C.S., "Found stake from one stump of one witness, planted stake with stone over." Hickory 12" S. 42¼° W. 299 lks., Hickory 10" S. 22½° E. 115¼ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found clay tile with pipe on East side, 2' West of North and South fence, 31.5 feet North of fence to West.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7-16-1997**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found clay tile is accepted a careful and faithful perpetuation of the position of the original corner. Placed Standard Sleeve over found clay tile, Accessories:

- Southwest corner of barn N. 15° E. 50.2'
- Nail in Northerly side 12" Hickory N. 70° E. 13.1'
- Nail in Northerly side 26" Oak West 121.5'
- Nail in Westerly side 20" Twin Cherry North 46.0'



Signed by *Allen H. McMachen*
Surveyor's Michigan License No. 16935

Date 7/25/97