

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Pavilion Twp.
Kalamazoo
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>3S.</u>	R	<u>10W.</u>	<u>C-12</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 2 PAGE 427
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 98 DEC 23 AM 3 53
 CLERK - REGISTER
Amelia Brown

Register of Deeds Stamp & File Number

I, Allen H. McMachen, in a field survey on March 16, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - Robert Clark, Jr., D.S., Set quarter Section post, Y. Oak 15" N. 51 1/2° W. 750 lks. W. Oak 12" North 1212 lks.
1888 - F. Hodgman, C.S., "Found old stake at angle of ditches at end of fence from the West and in line with fence North beyond swamp. Set post in bottom of ditch.

1952 - Kalamazoo County Surveyor's Office, Tile under ±18" of water in E. & W. fence, 6.5' East of fence to South at inter. of ditches, 6" Oak West 18.6', 4" Oak N. 50° E. 55.2', 4" Oak N. 20° E. 56.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found clay tile at base of fence post with "Do Not Disturb-Survey Marker" sign on it. Top of tile is 24" below water. Tile matches the 1952 witnesses to trees, however trees are now dead.

SURVEY &
 REMONUMENTATION
 FEB 08 1999
 SECTION

RAITIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 4/16/98 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found tile is accepted a careful and faithful perpetuation of the position of the original corner. Placed Standard Sleeve over tile (coord. value = N. 5000.0, E. 5000.0), Accessories:

Iron rod with red cap (existing) West 239.13' (coord. value = N. 5000.0, E. 4760.870)
 Iron rod placed N. 67° W. 223.62' (coord. value = N. 5088.753, E. 4794.752)
 Iron rod placed N. 44° W. 246.86' (coord. value = N. 5177.795, E. 4828.744)
 In swamp



Signed by *Allen H. McMachen*

Date 12/18/98

Surveyor's Michigan License No. 16935