

**SURVEY &  
REMONUMENTATION**

APR 27 1995

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

95 JAN 5 AM 9 46

**COMMISSION LAND CORNER RECORDATION CERTIFICATE,  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Kalamazoo Located In: Corner Code #  
(County)  
Pavilion Township  
1. Public Land Survey T 3 S R 10 W D-12  
T R  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

*James J. Jones*

CLERK - REGISTER  
LIBER 1 PG 1252

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on June 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

This Position Not Established by Original Government Surveyors.

1874: F. Hodgman, County Surveyor; Bisected 5-7 (north and South 1/4 Line) and planted stone.

Hickory 8" South 42 1/2° East 75 1/2 Lks  
Hickory 10" North 39 1/2° West 88 1/2 Lks

1972: Wilkins and Wheaton Engineering Company; Found iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 1/2" iron in monument box. Found flat stone (18" x 8" x 8") with notch on top about 18" deep and 0.22' North and 0.45' West of iron.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
9-15-94  
*R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-12 Center of Section 32, T. 3 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994. Found notched stone as set in 1874 survey by F. Hodgman. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Lowered stone and placed a 20" Harrison monument and monument box over stone.

Exist. Nail/Tab Cherry North 30° East 27.14'  
Exist. Nail/Tab in North Side Railroad Tie Fence Post South 79° East 43.43'  
Exist. Nail/Tab in North Side Power Pole North 88° West 28.70'  
Drill Hole in Top Concrete Fence Post West 18.60'  
Centerline 27th Street East 3.0'

Signed by *Robert E. Snell* Date 1-3-95  
Surveyor's Michigan License No. 9734