

**SURVEY &
REMONUMENTATION**

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'94 DEC 6 PM 3 56

James J. [Signature]

CLERK-REGISTER

For corners in
Kalamazoo

(County)

Located In:

Corner Code #

Pavilion Township

1. Public Land Survey	T 3 S R 10 W	D-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PG 1188

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on June 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1827 - U.S. Government Survey-Set Post, Corner to 1/4 Section

Wh. Oak 18" East 303 Lks
Wh. Oak 10" North 71½° West 33 Lks

1874 - F. Hodgeman, County Surveyor-Found stake from hole where one witness had been removed. Set stone and marked

Wh. Oak 12" North 5° West 437½ Lks
Pine 10" South 15½° East 90 Lks (not marked)

1888 - F. Hodgeman, County Surveyor-Found stone of resurvey and bearing trees in place. Set post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 - Found two (2) irons (½" x 18") in monument box and tile below (down 1').

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7/21/94 R. E. Snell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 South 1/4 Post Section 32, T. 3 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found 3" round tile as called for in remonumentation survey by F. Hodgeman in 1888 and is accepted as a careful and faithful perpetuation of the original corner's position. Removed irons and placed 12" of 20" Harrison monument over tile with monument box over.

Notch in Top of RR Rail Fence Corner North 32° East 51.19' CL "T" Avenue North 0.5'
PK Nail in Northeast Side 14" Cedar South 52° East 64.84' CL 27th Street East 0.55'
Northeast Corner of House Foundation South 08° West 59.13'
Northwest Corner of House Foundation South 29° West 65.40' North 1/4 Post Sec. 5,
Brady East 26.55'

Signed by Robert E. Snell

Date 12-3-94

Surveyor's Michigan License No. 9734