

NOV 25 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Pavilion Twp.

Kalamazoo  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>3S</u> R <u>10W</u>	E-10
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

LIBER  
 CLERK - REGISTER  
 2PAGE 351  
 STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 1998 OCT 22 AM 11 37  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on May 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP** 5-21-1998

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set 1/4 post:

White Oak 14" N. 47° W. 44 lks.  
 White Oak 18" N. 89° E. 32½ lks.

1888: F. Hodgman, County Surveyor; "found stone with brick under and bearing trees of re-survey standing. Set post."

Hickory 10" S. 45° E. 61 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1972: D. Ratekin, RLS#8781; L.C.R.C., L-1, P-13; 3/4" iron  
 Steel St. Sign Post S. 30° W. 45.1' 28" Bitter Hickory N. 60° W. 74.5'  
 Fence Corner Post N. 85° E. 28.2' 10" Pine N. 35° W. 68.1'  
 4" Oak S. 25° E. 78.1'

1998: Found 3/4" iron in monument box, further digging revealed 3" round tile, top broken 1.75' North and 0.55' West of surface iron. Tile was 10" below surface of road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10: West 1/4 post, Section 28, T. 3 S., R. 10 W., ratified on May 21, 1998 by the Kalamazoo County Remonumentation Program Peer Group and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile along side large stone. Tile was set by F. Hodgman, County Surveyor in 1888 Remonumentation survey. Placed tile sleeve over tile and 8" of 10" Harrison monument over and in monument box.

Nail/Tab in North Side Power Pole S. 56° E. 47.31'  
 PK Nail in North Side 10" Oak S. 28° E. 79.99'  
 PK Nail in West Side 15" Hickory S. 16° W. 100.99'  
 PK Nail in North Side 32" Hickory N. 70° W. 74.14'

Signed by Robert E. Snell  
 Surveyor's Michigan License No. 9734

Date 10-22-98