

SURVEY & REMONUMENTATION

MAY 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'96 APR 22 PM 4 23

For corners in
Kalamazoo
(County)

Located In:

Corner Code #

Pavilion Twp.

- | | | |
|--------------------------------------|------------------------------|-------------|
| 1. Public Land Survey | T <u>3</u> S. R <u>10</u> W. | <u>E-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

James D. Young

CLERK-REGISTER

LIBER 1 PAGE 1475

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert E. Snell, in a field survey on February 22, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827: United States Government Surveyors; set 1/4 Section post.

Y. Oak 14" S. 33° W. 49 lks.
Y. Oak 14" N. 71° W. 6 lks.

1888: F. Hodgman, County Surveyor; found stake standing in fence line. Hole of bearing tree Northwest 6 lks. Set post.

Wh. Oak 8" N. 04° E. 48½ lks.
Wh. Oak 10" S. 82½° E. 86 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1973: Wilkins & Wheaton Engineering Co.; found tile.

Clump Red Oak South 8.1'
24" Red Oak N. 15° W. 38.0'
18" Walnut S. 45° W. 17.0'

1996: Found tile at surface of ground with stones around. Found from 1973 witnesses.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3/21/96 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12: East 1/4 post, Section 32, T. 3 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on March 21, 1996, and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile as set by F. Hodgman in 1888 Remonumentation survey, placed remonumentation sleeve over tile.

Southeast corner brick garage (Hse. #10481)	N. 50° E.	45.97'
PK Nail in East Side Double 24" Red Oak	S. 05° W.	9.74'
PK Nail in North Side 24" Walnut	S. 70° W.	17.45'
PK Nail in West Side 26" Oak	N. 10° W.	39.17'

Signed by

Robert E. Snell

Date

4-19-96

Surveyor's Michigan License No. 9734