

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code#
Pavilion Township		
1. Public Land Survey	T <u>3S</u> R <u>10W</u>	<u>G2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY & REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary D. Hahn, in a field survey on December 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - Corner established by U.S. Deputy Surveyor, Robert Clark, Jr. Wh. Oak 8 S 33° E 45 L.
 Wh. Oak 9 N 39° E 49½ L.

1863 - F. Stimson: "Gov. corner lost + established by one"

1874 - F. Hodgeman: "Old corners good. Planted new stakes stone at a".

1888 - F. Hodgeman: "Found stake and stone and Red Oak bearing tree S 7° E 49 lks. in place. Set post Hickory 10" N 21½° E 92½ lks."

1993 - Robert Carr: L.C.R.C. L. 1 P. 990 Set ½" iron stake using single proportionate measurements along west line of section (section 3).

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 12-16-1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found ½" capped iron set by Carr 4' ± southwesterly of a 4" diameter metal fence post. The metal fence post has rusted away from its concrete base and is being held erect by two metal braces running west and north from the fence post. Excavated an extensive area around and under the fence post and the Carr iron. Removed the concrete fence post base in search of the post (tile) set in 1888 by F. Hodgeman. Found no evidence of the tile. Believe tile was removed during installation of the fence post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G2, East Quarter Post of Section 4, Town 3 South, Range 10 West. Ratified by the Kalamazoo County Remonumentation Peer Group on December 16, 1999. The position of the 4" diameter metal fence post is accepted as the best available evidence of the position of the original corner. Set a 30" Harrison Monument directly beneath said fence post.

Witness Ties: Set Mag. Nail in S. face 6" Cherry S 52° E 5.50'
 Set 60 d Nail in N. face 36" Cherry East 11.92'
 Set 60 d Nail in W. face 16" Cherry North 52.32'
 Set 60 d Nail in S. face 14" Cherry West 16.99'
 Fnd. capped iron "Carr 20704" S 23° W 3.80'



Signed by [Signature]
 Surveyor's Michigan License No. 38116

Date 12/30/99