

**SURVEY & REMONUMENTATION**

OCT 06 1997

2 COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Pavilion Twp.  
Kalamazoo  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>3S.</u>	R	<u>10W.</u>	<u>G-8</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous	S	_____	T	_____	_____
Property in Section	S	_____	T	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

LIBER  
 CLERK - REGISTER  
 J. J. [Signature]  
 PAGE 178  
 297 JUL 29 PM 3 57  
 STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, Allen H. McMachen, in a field survey on June 3, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1826 - Robert Clark, D.S.  
 Set quarter Section post, Beech 11" S. 16° W. 17½ lks.  
 Beech 13" N. 23° W. 17 lks.  
1874 - F. Hodgman, Surveyor, "At East quarter post found stake from one witness standing. Set stone and marked Beech 14" S. 71° E. 85½ lks."

1888 - F. Hodgman, C.S.  
 "Found stone of resurvey in place, set post. Cherry N. 7½° W. 62 lks., Maple 10" N. 87¼° W. 62 lks."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found clay tile next to 2' X 2' stone, in line with fence North and 1.4' below grade.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 6-19-1997 [Signature]

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found clay tile is accepted a careful and faithful perpetuation of the position of the original corner. Placed Standard Sleeve over found clay tile, Accessories:

- Nail in South side 36" Ash S. 85° E. 34.05'
- Nail in Northeast side 26" Maple S. 50° E. 54.50'
- Nail in Southeast side 18" Cherry S. 35° W. 16.02'
- Nail in West side 20" Maple N. 15° W. 39.38'



Signed by Allen H. McMachen  
 Surveyor's Michigan License No. 16935

Date 7/14/97