

SURVEY & REMONUMENTATION

MAY 16 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'96 MAR 13 PM 3 42

For corners of **COMMISSION**
Kalamazoo
(County)
Pavilion Twp.

Located In: Corner Code #

- | | | |
|--------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 3 S, R 10 W. | G-12 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

James J. Sprung
CLERK-REGISTER

LIBER 1 1450

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on January 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established; monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1827: Original United States Government Surveyors; set 1/4 Section post.

W. Oak 48" N. 55° W. 115 lks.
W. Oak 20" S. 68° W. 96 lks.

1888: F. Hodgman, County Surveyor; found stake in place at angle of fence.

W. Oak 12" N. 82° W. 86 lks.

: Gove Associates; tile, stone, 2" iron pipe. 30" W. Oak N. 80° W., 60.00'; Fence post South 6.2'; 8" W. Oak, S. 45° W. 42.00'; 12" Elm N. 55° E. 109.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 3" round tile with "x" on top 22" below surface, 2 (1/2"x18") irons were over tile. A 2" round steel pipe with square top is 0.35' South of tile and below surface. Tile is on North side of G.T.W. Railroad North right-of-way fence and 50'+ West of drain.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
2-15-96 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12: East 1/4 Post Section 33, T. 3 S., R. 10 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on February 15, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top as set by F. Hodgman in 1888 Remonumentation Survey. Placed a 20" Harrison Monument over tile and placed found irons along side of monument.

PK Nail in East Side	14" Elm	S. 50° E. 9.95'
Exist. Nail/Tab in West Side	Fence Post	South 6.05'
Southeast corner	Concrete Block Retaining Wall	N. 40° W. 30.95'
PK Nail in North Side	19" Oak	S. 50° W. 42.82'

Signed by *[Signature]*
Surveyor's Michigan License No. 9734

Date 3-12-96