

AUG 22 1995

COMMISSION

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'95 MAR 23 PM 4 09

For corners in PAVILION TWP.

KALAMAZOO  
(County)

Located In:

Corner Code #

- 1. Public Land Survey            T 3 S R 10 W            I-2
- T     R                            \_\_\_\_\_
- T     R                            \_\_\_\_\_
- T     R                            \_\_\_\_\_
- 2. Property Controlling        S     T     R                    \_\_\_\_\_
- in Section                    S     T     R                    \_\_\_\_\_
- 3. Miscellaneous                S     T     R                    \_\_\_\_\_
- Property in Section        S     T     R                    \_\_\_\_\_

*James J. [Signature]*

CLERK-REGISTER

LIBER

1 PG 1283

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen field survey on January 12, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1827 - R. Clark, D.S., Set Quarter Section Post  
 W. Oak 13" N. 62° W. 39 lks.  
 W. Oak 16" N. 75° E. 14½ lks.

1888 - F. Hodgeman, C.S., Found Stake S. 75° W. 14½ lks. from stump of bearing tree, Set Post.  
 W. Oak 16" S. 47½° E. 23 lks.  
 Y. Oak 3" N. 3° W. 34½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile 0.4' below surface, 1.2' South of fence corner.

RATIFIED  
 BY KALAMAZOO COUNTY  
 REMONUMENTATION  
 PEER GROUP

2/16/95  
*R. J. [Signature]*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Standard sleeve over existing Clay Tile. Accessories:

- Nail & Tab in S.E. Face 7" Cherry N. 35° E. 3.51'
- Nail & Tab in S. Face 18" Hickory EAST 9.80'
- Nail & Tab in W. Face 6" Cherry S. 05° W. 13.41'
- Nail & Tab in S. Face 10" Oak WEST 27.27'

Signed by Allen H. McMachen  
 Surveyor's Michigan License No. 16935

Date 3/22/95