

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'95 DEC 14 PM 3 30

For corners in Pavilion Township  
Kalamazoo  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 3S. R 10W. I-8
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*James Young*  
CLERK-REGISTER

LIBER 1 1409

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

6. IWM Job No. 27007

I, Allen H. McMachen, in a field survey on December 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1862 - U.S. Government Survey  
Set ¼ Section Post  
W. Oak 9" S. 53° W. 6 lks.  
W. Oak 14" N. 21° E. 25 lks.

1888 - F. Hodgman, C.S.  
"Rock Bounds" by R. Nutting  
Hickory 4" N. 68° E. 19½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found large stone with drill hole. Stone approximately 3' wide by 4' tall.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
1-19-95

*R. E. S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Stone with drill hole is accepted as the best available evidence of the position of the original corner. Unable to move stone, placed iron securely in drill hole, Accessories:

- "PK" Nail in South face R.R. tie fence post East 5.34'
- "PK" Nail in South face R.R. tie fence post West 1.71'
- Nail & Tab in N.W. face 24" Hickory N. 55° E. 12.45'
- Nail & Tab in South face 6" Cherry S. 60° W. 7.99'



Signed by *Allen H. McMachen*

Date 12/13/95

Surveyor's Michigan License No. 16935