

**SURVEY & REMONUMENTATION**

MAY 16 1996

COMMISSION

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'96 APR 22 PM 4 23

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Kalamazoo  
(County)

Located In:

Corner Code #

Pavilion Twp.

- |                                      |                              |             |
|--------------------------------------|------------------------------|-------------|
| 1. Public Land Survey                | T <u>3</u> S. R <u>10</u> W. | <u>I-13</u> |
|                                      | T _____ R _____              | _____       |
|                                      | T _____ R _____              | _____       |
|                                      | T _____ R _____              | _____       |
| 2. Property Controlling in Section   | S _____ T _____ R _____      | _____       |
|                                      | S _____ T _____ R _____      | _____       |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____      | _____       |
|                                      | S _____ T _____ R _____      | _____       |

*James J. Young*  
CLERK-REGISTER

LIBER 1 PAGE 1477

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	8	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on February 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1827: United States Government Surveyors; set post, corner to Sections 34 and 35.  
Beech 8" N. 60° E. 27 lks.  
Beech 14" N. 80½° W. 25 lks.

1888: F. Hodgman, County Surveyor; found stone, brick and one bearing tree of re-survey in place. Set post.  
Maple 4" S. 22½° E. 92½ lks.  
Maple 4" S. 67° E. 136½ lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1945: Wilkins & Wheaton Engineering Co.; found tile.  
24" Maple S. 22½° E. 59.82'  
Maple S. 67° E. 89.53'  
18" Elm North 28.10'  
Sign 32nd St./"T" Ave. S. 80° W.

1996: Found tile in monument box off Northwest side of road. Pinch pipe in monument box (NW corner Section 2, T. 4 S., R. 10 W.) West 5.31'

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**

3/21/96 *R.E.S.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-13: Southeast corner, Section 34, T. 3 S., R. 10 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on March 21, 1996, and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile in monument box. The tile was set by F. Hodgman in 1888 Remonumentation survey. Placed remonumentation sleeve over tile in monument box.

PK Nail in East Side 14" Ash N. 10° E. 61.24'  
PK Nail in North Side 36" Maple S. 66° E. 90.37'  
PK Nail in South Side 9" Pine S. 46° W. 37.77'  
Exist. Nail/Tab in West Side East Gate Post N. 02° W. 38.42'

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 4-19-96