

**SURVEY &
REMONUMENTATION**

MAY 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'96 MAR 13 PM 3 42

For corners in
Kalamazoo
(County)

Located In:

Corner Code #

Pavilion Twp.

- | | | | | | | |
|---|---|-------------|---|--------------|-------------|-------|
| 1. Public Land Survey | T | <u>3</u> S. | R | <u>10</u> W. | <u>J-03</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling
in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous
Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

James D. Young
CLERK-REGISTER

LIBER **1 1452**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3									●			
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on January 23, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827: Original United States Government Survey; set 1/4 Section post.

Aspen 10" N. 56⁰ E. 192 lks.
Aspen 12" N. 66⁰ W. 980 lks.

1888: F. Hodgman, County Surveyor; found stake standing at intersection of fences. Set post, no trees.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found tile (3" round with "x") on top. The tile is set in concrete at the base of a fence corner.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**
2-15-96

R 28

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-03: South 1/4 post Section 2, T. 3 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on February 15, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top set in concrete base of fence corner, top 3" broken. Tile set by F. Hodgman, County Surveyor in 1888 Remonumentation survey. Tile in concrete is retained as monument.

PK Nail in West side	15" W. Cherry	N. 10 ⁰ W.	8.37'
PK Nail in East side	15" Oak	N. 20 ⁰ W.	14.34'
PK Nail in North side	12" W. Cherry	N. 85 ⁰ W.	16.91'
PK Nail in East side	3" Oak	South	3.66'

Signed by Robert E. Snell

Date 3-12-96

Surveyor's Michigan License No. 9734