

**SURVEY & REMONUMENTATION**

SEP 17 1998

**SECTION**

For corners in

Kalamazoo

Pavilion Twp.

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

Located In:

Corner Code #

T 3S R10W	J-07
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECORDS & DEEDS  
96 OCT 18 AM 11 32

LIBER 2 PAGE 068

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on April 26 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP 6-20-1996**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1827: United States Government Surveyors; set 1/4 Section post.

W. Oak 18" S. 40° W. 16 lks.  
W. Oak 8" S. 85° E. 36 lks.

1888: F. Hodgman, County Surveyor; found "rock bounds" set by Nutting.

Butternut 6" N. 15° W. 37 lks.  
Butternut 6" N. 67° W. 86½ lks.

(Note: "rock bounds" retained as monument in 1888).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1949: Wilkins & Wheaton Engr. Co.; found stone, drill hole in top, brought up with iron rod.

24" Butternut N. 67½° W. 56.0'  
16" Butternut N. 70° W. 39.75'  
Telephone Pole S. 68° E. 63.23'

1972: John Kester, R.L.S. #16046; found iron over stone: 20" Oak S. 32° E., 79.35', Telephone Pole S. 67° E., 61.26', 20" Ash N. 75° W., 38.38'

1996: Found iron (5/8" x 12") in monument box over drill mark in stone. A Mr. Webster said stone with hole in it has been there for the last 75 years, that he can remember.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-07: South 1/4 post, Section 14, T. 3 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on June 20, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found iron over stone in monument box, the stone being set by R. Nutting and verified by F. Hodgman in 1888. Placed 10" of 20" Harrison monument over drill mark within existing monument box.

PK Nail in South Side 18" Ash N. 50° E. 54.82'  
PK Nail in West Side 32" Oak S. 30° E. 80.48'  
PK Nail in South Side Power Pole S. 52° W. 89.63'  
PK Nail in West Side 20" Ash N. 20° W. 31.50'

Signed by Robert E. Snell  
Surveyor's Michigan License No 9734

Date 10-14-96