

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'95 DEC 14 PM 3 30

For corners in Pavilion Township  
Kalamazoo  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	3S.	R	10W.	J-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

*James Young*  
CLERK-REGISTER

LIBER 1 1408

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

6. IWM Job No. 27007

I, Allen H. McMachen, in a field survey on December 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

No historic information found

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone with iron rod in drill hole. Line between stone at W $\frac{1}{4}$  cor. and  $\frac{3}{4}$ " square iron at E $\frac{1}{4}$  cor. is South 1.17'. Line between iron rod at N $\frac{1}{4}$  and iron rod at S $\frac{1}{4}$  cor. is 0.08' West of found stone. Stone 0.6' below grade.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
2-16-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This position not established by original Government Surveyors. Found stone with iron is accepted as the best available evidence of the position of the corner. Unable to remove stone due to size. Placed Harrison Monument over stone, set in concrete with Mon. Box over, Accessories:



"PK" Nail in South face of U. Pole N. 75° W. 68.78'  
S.E. corner house N. 30° E. 302.33'  
Nail & Tab in S.E. face 26" Hickory N. 20° E. 95.92'  
Nail & Tab in S.E. face 14" Walnut N. 40° E. 42.15'

Signed by Allen H. McMachen  
Surveyor's Michigan License No. 16935

Date 12/13/95