

1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
'95 AUG 24 PM 3 58

For corners in PAVILION TOWNSHIP  
KALAMAZOO Located in:

Corner Code #

1. Public Land Survey	T	<u>3</u>	S	R	<u>10</u>	W	<u>J-11</u>
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Section	S		T		R		
	S		T		R		

*James J. Jones*  
CLERK-REGISTER

LIBER 1 1320

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Allen H. McMachen field survey on March 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826 - R. Clark, D.S. Set 1/4 Sec. Post Wh. Oak 11" S. 80° E. 23 1/2 lks. Wh. Oak 8" S. 53° W. 9 lks. 20" Wh. Oak Station Tree mentioned in notes 1.43 CH. West of corner
- 1874 - F. Hodgman, Stake lost but stump of station tree 143 lks. West standing
- 1888 - F. Hodgman, C.S. Stone of resurvey and bearing trees standing, Set Post.
- 1884 - F. Hodgman, C.S. Found Stake hole 143 lks. East of station tree, Set marked Stone with brick around and marked Wh. Oak 12" S. 26 1/2° E. 44 lks Wh. Oak 8" N. 55° E. 8 1/2 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 1" Iron rod per 1985 I.W.M. Wits., removed 1" rod and found base section of Tile. Telephone cable is directly over Tile and 2.4' below surface. Placed Harrison Mon. over Tile and above said cable. Found 1' Iron was found directly over Tile base.
- 1985 - I.W.M. Found broken top section of Tile, Base section of tile in good condition, 3.5' below surface, Set 1" Iron rod 3' long over Tile base, Witness: 12" Oak N. 60° W. 23.72' TW. 24" Oak N. 35° E. 35.50' 14.4' Northerly of painted 30" Elm N. 45° E. 67.10'

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
4-20-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison Monument over base section of Tile and Monument box over. Accessories:

- Nail & Tab in W. Face 16" Oak N. 70° W. 23.74'
- Nail & Tab in E. Face TW. 30" Oak N. 40° E. 35.40'
- Nail & Tab in E. Face 16" Oak N. 50° E. 97.20'
- Nail & Tab in N. Face U. Pole N. 75° E. 85.99'



Signed by *Allen H. McMachen*

Date 5/24/95

Surveyor's Michigan License No. 16935