

**SURVEY &
REMONUMENTATION**

APR 27 1995

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'95 JAN 5 AM 9 46

For corners in

<u>Kalamazoo</u> <small>(County)</small>	Located in:	Corner Code #
<u>Pavilion Township</u>		
1. Public Land Survey	T <u>3</u> S R <u>10</u> W	<u>J-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James J. [Signature]
CLERK-REGISTER

LIBER 1 PG 1251

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 31, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

This Position Not Established by Original Government Surveyors.

1884: F. Hodgman, County Surveyor; Center 1/4, at intersection of Quarter Lines. Set purple stone (18" x 6" x 8")

Maple 12" South 79° East 224 Lks

1993: Roger Stephenson, Surveyor; Set railroad spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found a railroad spike at surface. Found purple stone (18" x 6" x 8") 18" below surface, 3.0' North and 2.5' West of railroad spike.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-15-94
[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-12 Center of Section 35, T. 3 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994. Found purple stone as set by F.Hodgman in 1884 survey. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Lowered stone and placed a 20" Harrison monument and monument box over stone.

Centerline of "T-S" Avenue	North	1.2'	In Tree
PK Nail in West Side	10" Walnut	North	68.76' Line N&S
PK Nail in West Side	9" Cherry	South 30° East	58.73'
Top Northwest Corner of	4" Metal Gate Post	South 22° East	51.26'
PK Nail in Face	Railroad Tie Fence Corner	South 05° West	26.65'

Signed by *Robert E. Snell* Date 1-3-95
Surveyor's Michigan License No. 9734