

**SURVEY &  
REMONUMENTATION**

APR 27 1995

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

94 NOV 18 AM 10 52

For corners in

Kalamazoo (County)	Located In:	Corner Code #
Pavilion Township		
1. Public Land Survey Closing Corner	T ___ R ___ T 3S R 10W	K-1
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	

*[Signature]*  
CLERK-REGISTER

LIBER 1 PG 1178

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John G. Kester, in a field survey on August 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner Post established by U S Government Deputy Surveyor, Robert Clark Jr., 1826, Accessories: Beech 7 S 59 W 41½, D O 9 S 11 E 42.  
Remonumentation by F. Hodgman, 1888, Found Stone of resurvey and Bearing Tree S W was in place. Set Post (solid clay tile) with Stone beside 29 lks East of Post Corner to Sections 35 & 36, T2S-R10W.  
LCRC by Allen H. McMachen in 1978, Railroad Spike, Accessories: 8" Hickory S 75° W 103.09', 24" Walnut N 10° E 91.33'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Original Corner and Accessories not recovered.  
Post (solid clay tile) with Stone beside set during remonumentation by Hodgman and Accessories not recovered.  
Found Railroad Spike called for in LCRC by McMachen in 1978, Accessories good. This was only evidence found in 8'x12'x6' deep excavation. It appears that all other evidence was removed when road was rebuilt around 1920.

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**  
10/21/93 *[Signature]*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-1, Northeast Closing Corner of Section 2, T3S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on October 21, 1993. Found Railroad Spike at recorded Jog and as called for in 1978 LCRC by McMachen and is accepted as the best available evidence of the position of the Original Closing Corner. Replaced Railroad Spike with 30" Harrison Monument and placed Monument Box over Corner.  
Set P.K. Nail in P.P. N45°E 70.50'  
Set P.K. Nail in 9" Hackberry East 68.70'  
Set P.K. Nail in T.P. stub N60°W 71.20'  
S.W. Corner Concrete Curb & Gutter S35°W 68.85'  
Southeast Corner Section 35, T2S-R10W, West 19.14'

Signed by *[Signature]* Date November 15, 1994

Surveyor's Michigan License No. 16046  
Kalamazoo County Road Commission