

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 JAN 5 AM 9 46

For corners in

Kalamazoo

(County)

Located In:

Corner Code #

Pavilion Township

1. Public Land Survey	T <u>3</u> S	R <u>10</u> W	<u>K-9</u>
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

J. J. J.

CLERK-REGISTER

LIBER

1 PG 1255

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 31, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826: U.S. Government Surveyors; Set Post Corner to Sections 23, 24, 25 and 26.

W. Oak 8" North 35° West 160 Lks
W. Oak 9" South 55½° West 100 Lks

1888: F. Hodgman, County Surveyor; Lost. Set Post midway between 1/4 Post North and South, 40.21½ Chains from 1/4 Post East and 40.26½ Chains from 1/4 Post West.

Y. Oak 24" North 11° West 76 Lks
Hickory 12" North 55° East 100 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1966: Wilkins and Wheaton Engineering Company; Found tile 3.5' deep, raised with iron.

Railroad Crossing Sign North 84° East 123.40'
Railroad Crossing Sign South 18° East 66.50'
Railroad Crossing Sign South 20° West 33.68'
6" Willow North 40° East 62.35'

1994: Found iron in monument box. Found tile down about 4'.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7-21-94 *R. E. S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Southeast Corner Section 23, T. 3 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 27, 1994. Found 3" round tile as called for in 1888 remonumentation survey by F. Hodgman and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed a 20" Harrison monument and monument box over tile at surface of the road.

In Centerline of 34th Street
Notch in Northeast Bolt in Base of Railroad Crossing Gate South 18° East 77.05'
Notch in Northeast Bolt in Base of Railroad Crossing Gate South 40° West 34.32'
PK Nail in South Side South Branch of 20" Double Oak North 19° West 96.25'
PK Nail in West Side 50" Willow North 38° East 62.35'
Centerline of "R" Avenue to West North 4.9'

Signed by *Robert E. Snell* Date 12/30/94

Surveyor's Michigan License No. 9734