

FEB 08 1999

LIBER

2 PAGE 412

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 3 05
Clerk - Registrar

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code#
<u>Pavilion Township</u>		
1. Public Land Survey	T <u>3S</u> R <u>10W</u>	<u>L-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Gary D. Hahn, in a field survey on November 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - Established by U.S. Deputy Surveyor Robert Clark, Jr., N 4 E 30 1/2 lks. Y. Oak 20 N 89 W 34 lks.

1863 - F. Stimson - "Found stone at 1/4 corner North side of sec. set by Nutting 2 feet deep. Hole drilled in top."

1870 - F. Hodgman - "At the 1/4 post of 13 and 24 a large stone with a hole drilled in it is set. Planted by R. Nutting surveyor"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 - Original monument and accessories not recovered. Found 1/2" dia. 8" long rod in 2" dia. 3" long pipe in road surface. Removed. Found 10" x 12" round stone with drill hole 28" below road surface. Found two broken pieces of a clay tile lying next to stone. Drill hole in stone was 0.15' south and 0.12' west of surface rod location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7, South Quarter Post Section 13, Town 3 South, Range 10 West, ratified by Kalamazoo County Remonumentation Peer Group on December 17, 1998. Position of the drill hole in stone is accepted as a careful and faithful perpetuation of the position of the original corner. Set 16" Harrison Monument in a Monument Box directly over drill hole in tile.

Witness Ties:

- Set Mag. Nail in 24" Hickory N 65 E 64.13'
- Set Mag. Nail in P.P. N 5 E 57.06'
- Set Mag. Nail in wood fence post N 40 W 40.17'
- Set Mag. Nail in 10" Oak S 40 W 51.25'

Signed by [Signature]
Surveyor's Michigan License No. 38116

Date 12/21/98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983 REVISED OCT., 1995

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

12/17/98
[Signature]

