

**SURVEY & REMONUMENTATION**

JUL 23 1997

LIBER 2 PAGE 148

7. COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

2- For corners in Pavilion Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>10W</u>	<u>1-09</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORDS  
1997 JUN 24 PM 1 17  
Clerk - Register  
*[Signature]*  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on March 31, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1826: United States Government Surveyors; set 1/4 Section post.

Wh. Oak 10" S. 10° W. 25 lks.  
Wh. Oak 36" N. 62° W. 40 lks.

1888: F. Hodgman, County Surveyor; "Found stone of resurvey and bearing tree N. 49° W. 72 lks. standing. Set post" Maple 12" N. 47 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1966: Wilkins & Wheaton Engr. Co.; found tile.

16" Oak South 50.10'  
24" Maple N. 67° W. 71.10'  
Power Pole N. 15° E. 71.35'  
16" Maple S. 89° W. 62.47'  
26" Maple N. 19° W. 103.5'

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
4-17-1997 *[Signature]*

1997: Found 3" round tile with "x" on top in monument box in center line of 35th Street and 2.7' South of center line of "R" Avenue.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-09: South 1/4 post, Section 24, T. 3 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on April 17, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top as set by F. Hodgman, County Surveyor in a 1888 Remonumentation Survey in a monument box. Placed remonumentation sleeve over tile.

PK Nail in West Side Power Pole N. 22° E. 71.74'  
PK Nail in West Side 22" W. Cherry S. 54° E. 47.46'  
PK Nail in East Side 16" Maple S. 14° E. 29.65'  
PK Nail in South Side 30" Maple N. 65° W. 72.26'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 6-18-97