

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 376  
98 NOV 23 PM 2 57  
STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
CLERK - REGISTER  
Register of Deeds Stamp & File Number

For corners in Pavilion Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T3S R10W	L-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on Aug. 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP 9-17-1998**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set 1/4 post.

White Oak 8" S. 81° E. 61½ lks.  
White Oak 8" S. 62° W. 95 lks.

1888: F. Hodgman, County Surveyor; "'Rock Bounds' by Nutting. Set 1 foot post on top of rock."

Yellow Oak 12" S. 37° E. 42 lks.  
Maple 5" S. 12° E. 43½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1977: Wilkins & Wheaton Engr. Co.; found iron in monument box.

1977: A. McMachen, RLS #16935; L.C.R.C. L-1, P-733, iron in monument box.

26" Maple N. 30° W. 33.01'  
18" Oak North 35.93'  
54" Ash S. 10° E. 28.83'

1998: Found ½"x18" iron with cap in monument box 6" below surface. Found stone with drill hole 24" below surface of road. Surface iron was 0.02' East and 0.07' South of drill hole in stone. Noted nail/tab in East side large dead tree S. 12° E. 28.91' Note A. above "1888 Maple 5" S. 12° E. 43½ lks." = 28.71'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11: South 1/4 post, Section 25, T. 3 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 17, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found large stone set by "Nutting" and verified by F. Hodgman, County Surveyor, in 1888 Remonumentation survey below ½"x18" iron. Placed 20" Harrison monument over stone with drill hole and adjusted monument box.

PK Nail in West Side 13" Maple S. 40° E. 40.87'  
PK Nail in North Side 8" Maple S. 68° W. 53.42'  
PK Nail in South Side 31" Maple N. 60° W. 59.40'  
PK Nail in West Side (over Nail/Tab) 32" Maple N. 26° W. 32.95'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 11-20-98