

FEB 08 1999

LIBER 2 PAGE 434

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Pavilion Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>10W</u>	<u>M-08</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 29 AM 11 26
Register of Deeds Stamp & File Number
CLERK - REGISTER

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Aug. 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 9-17-1998

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors; set 1/4 Section post.
Wh. Oak 9" S. 43¹/₂⁰ W. 62 lks.
Wh. Oak 10" N. 31¹/₂⁰ W. 157 lks.
- 1888: F. Hodgman, County Surveyor; "'Rock Bounds" by Nutting and side stones East and West 50 lks."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1952: Wilkins & Wheaton Engr. Co.; found drilled stone no witnesses.
- 1975: Allen McMachen, RLS#16935; L.C.R.C. L-1, P-593, iron in ring in centerline inter-section.
Utility Pole N. 45⁰ E. 34.92' Utility Pole S. 45⁰ E. 30.21'
Utility Pole S. 45⁰ W. 33.10'
- 1998: Found 3/8"x8" iron in sleeve over stone. Surface iron was 0.20' South and 0.10' East of drill hole in stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-08: East 1/4 post, Section 24, T. 3 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 17, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found large stone with drill hole as set by "Nutting" previous to 1888 and verified by F. Hodgman, County Surveyor in 1888 Remonumentation survey. Placed 6" Harrison monument in concrete with monument box over.

Nail/Tab in South Side	Power Pole	N. 45 ⁰ E.	35.01'
PK Nail in East Side	Power Pole	S. 45 ⁰ W.	32.61'
PK Nail in South Side	Power Pole	S. 35 ⁰ E.	67.88'
Nail/Tab in South Side	Power Pole	S. 40 ⁰ E.	30.05'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-29-98