

FEB 08 1999

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 98 NOV 23 PM 2 57
 Clerk - REGISTER

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Pavilion Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>10W</u>	<u>M-09</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on Aug. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 4-17-1998

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors; set corner post to Sections 24 & 25.
 White Oak 6" S. 18⁰ W. 28 lks.
 White Oak 6" N. 55⁰ W. 22 lks.
- 1888: F. Hodgman, County Surveyor; found stone with stake under having a nail driven in 104 lks. South of corner of Section 19 & 30. Set post.
 Butternut 12" S. 63⁰ W. 56 lks.
 Maple 12" N. 27⁰ W. 97 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1952: Wilkins & Wheaton Engr. Co.; found tile.
 Date Unknown: Acro Engr.; tile found 1' down, 30" Maple N. 50⁰ W. 67.4', Utility Pole S. 40⁰ E. 41.5', 10" B. Walnut S. 25⁰ W. 84.3', RR iron fence post NE 47.25'
- 1998: Found 3/8"x8" iron in 2"x2" sleeve 3" below surface, found tile 15" below surface. Top scared and broken. Surface iron 0.07' South and 0.09' East of tile.
 Noted iron in 2" sleeve in monument box South 68.60' (Southwest corner Section 19, T. 3 S., R. 9 W.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-09: Southeast corner of Section 24, T. 3 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 17, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile 15" below surface under 3/8"x8" iron in sleeve. Tile was set in 1888 Remonumentation survey by F. Hodgman, County Surveyor. Placed remonumentation tile sleeve over tile and 10" Harrison monument in monument box.
- | | | | |
|-----------------------------------|------------|-----------------------|--------|
| Lowest 16d Nail in Southeast Side | Power Pole | N. 36 ⁰ E. | 52.60' |
| PK Nail in Northwest Face | Power Pole | S. 32 ⁰ E. | 44.52' |
| PK Nail in North Side | 22" Maple | S. 88 ⁰ W. | 50.08' |
| PK Nail in North Side | 32" Maple | N. 54 ⁰ W. | 59.87' |

Signed by Robert E. Snell
 Surveyor's Michigan License No. 9734

Date 11-20-98