

FEB 08 1999

LIBER 2 PAGE 378

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Pavilion Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T 3S R 10W	M-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 NOV 23 PM 2 57
J. J. Johnson
CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert E. Snell, in a field survey on Aug. 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; set 1/4 Section post.

White Oak 6" S. 27 1/2° W. 59 lks.
White Oak 12" N. 16 1/2° W. 32 lks.

1888: F. Hodgman, County Surveyor; "Found stake and stone 96 lks. North of 1/4 post of Section 30, Climax and set post."

Blk. Walnut 6" S. 87° E. 54 lks.
Maple 4" S. 50° W. 63 1/2 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1952: Wilkins & Wheaton Engr. Co.; iron and tile, NE corner House SW 92.15'

8" Oak N. 30° W. 77.25'
6" Walnut S. 45° E. 48.32'

1998: Found 3/8"x11" iron at surface, found 1/2"x12" iron 8" below surface, found tile 20" below surface 0.05' North and 0.07' West of surface iron. Top was scared.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 9-17-998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10: East 1/4 post, Section 25, T. 3 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 17, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile 20" below surface under 2 irons. Tile was set in 1888 Remonumentation survey by F. Hodgman, County Surveyor. Placed remonumentation sleeve over tile and 10" Harrison monument on top in monument box.

PK Nail in North Side 22" Walnut
PK Nail in South Side 32" Walnut
PK Nail in South Side 30" Maple
PK Nail in South Side 24" Walnut

N. 64° E. 33.55'
S. 48° E. 40.54'
S. 52° W. 42.07'
N. 46° W. 40.97'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 11-20-98