

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Pavilion Twp.

Kalamazoo Located In: Corner Code #
(County)

1. Public Land Survey T 3S R 10W M-12
T R
T R
T R

2. Property Controlling in Section S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER
CLERK - REGISTER
2 PAGE 380
98 NOV 23 PM 2:58
STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on Aug. 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 9-17-1998

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors; set 1/4 Section post.
Beech 8" N. 49° W. 14 lks.
Beech 6" S. 42° W. 99 lks.
- 1888: F. Hodgman, County Surveyor; "Found old stake hole 44 lks. South of the 1/4 post of Section 31. (Climax). Set post."
Elm 5" S. 32° E. 85 lks.
Elm 4" N. 87° E. 42½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1952: Wilkins & Wheaton Engr. Co.; found tile - fence to East North 3.65'
30" Elm S. 32° E. 56.11'
12" Walnut N. 60° W. 30.53'
16" W. Oak N. 85° W. 86.8'
- 1977: A. McMachen, RLS #16935; L.C.R.C. P=1, L-733, Iron in pipe, 24" Walnut N. 30° W. 79.71', RR fence corner S. 45° E. 43.65', 6" Maple S. 30° E. 75.50'
- 1998: Found 3/8"x6" iron in 2"x2" sleeve. Found 3" round tile 2' below surface directly under iron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-12: East 1/4 post, Section 36, T. 3 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 17, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile 2' below surface, under 3/8"x6" iron. Tile set in 1888 Remonumentation survey by F. Hodgman, County Surveyor. Placed remonumentation sleeve over tile with 10" Harrison monument in monument box over tile.
PK Nail in North Side 12" Maple S. 50° E. 51.22'
PK Nail in West Side 38" Maple S. 20° E. 76.22'
PK Nail in North Side 16" Walnut N. 78° W. 38.26'
Nail/Tab in South Side 24" Walnut N. 10° W. 79.75'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 11-20-98