



LC-000051
Page: 1 of 1
10/28/1999 03:11P
BK-2 Pg-504

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

For corners in

Kalamazoo

Located In:

Corner Code#

(County)

Pavilion Twp.

1. Public Land Survey

T 3S R 10W

M12

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Gary D. Hahn, in a field survey on October 20, 1999

do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Please refer to previously recorded Land Corner Recordation Certificate Liber 2, Page 380 for history.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument box and Harrison monument over previously ratified tile with remonumentation sleeve were removed during 1999 reconstruction of 36th Street. After the leveling coarse of asphalt was placed the tile and sleeve were excavated and found to be undisturbed. A 16" Harrison Monument was set over the tile in a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M12, East Quarter Post Section 36, Town 3 South, Range 10 West. Ratified by the Kalamazoo County Remonumentation Peer Group on September 17, 1998. See previously recorded Land Corner Recordation Certificate Liber 2, Page 380.

Witness Ties: Found PK nail in North side 12" Maple S 50 ° E 51.22'
Found PK nail in West side 38" Maple S 20 ° E 76.22'
Found PK nail in North side 16" Walnut N 78 ° W 38.26'
Found nail w/tab in South side 24" Walnut N 10 ° W 79.75'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5		4		3		2		1			
3													
4	7	8		9		10		11		12			
5													
6	18	17		16		15		14		13			
7													
8	19	20		21		22		23		24			
9													
10	30	29		28		27		26		25			
11													
12	31	32		33		34		35		36			
13													

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-17-1998



Signed by _____
Surveyor's Michigan License No. 38116

Date 10/18/99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983 REVISED OCT., 1995