

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KALAMAZOO

(County)	Located In:	Corner Code \neq
1. Public Land Survey	T <u>35</u> R <u>11W</u>	<u>A-7</u>
	T <u>35</u> R <u>11W</u>	<u>A-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GARY C. BILOW, in a field survey on AUGUST 15, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-7) CORNER ESTABLISHED BY U.S. GOVERNMENT DEPUTY SURVEYOR ROBERT CLARK, 1827, AT A FALLING OF "37 N OF STK". ACCESSORIES: W. OAK 8 S67E 51, DO 10 N23E 200. CORNER SHOWN IN MICHIGAN STATE HIGHWAY DEPARTMENT RECORDS (BOOK 5 OF 8, PAGE 8, PROJECT NO. 39013 RM, DATED DEC. 1959) AS FOUND 3/8" IRON AND WITNESSED AS FOLLOWS: P. POLE N22W 78.53', 6" OAK S36E 62.62', 21" OAK S87E 89.93'. CORNER RECORDED UNDER ACT 74, P.A. 1970 (LCRC LIBER 1, PAGE 591) DEC. 1975 AS IRON IN MONUMENT BOX. RECORD ACCESSORIES ARE AS FOLLOWS: U.P. N20W 78.53', 6" OAK S40E 62.62', IRON ROD EAST 33.0'.

(A-8) CORNER NOT SET IN ORIGINAL SURVEY. FOUND NO RECORD OF SUBSEQUENT ESTABLISHMENT. CORNER SHOWN ON RECORDED PLATS OF "STAGECOACH TRAILS NO. 1" (LIBER 31 OF PLATS, PAGE 3) AND "STAGECOACH TRAILS NO. 2" (LIBER 33 OF PLATS, PAGE 27).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-7) ORIGINAL CORNER POST AND ACCESSORIES NOT RECOVERED. FOUND AND ACCEPTED 1/2" REINFORCING BAR IN MONUMENT BOX. MSHD TIE TO POWER POLE AND RECORDED TIE TO UTILITY POLE CHECK. GLO FALLING TO STANDARD CORNER CHECKS TO SOUTH.


(A-8) FOUND 1/2" REINFORCING BAR ON LINE BETWEEN THE STANDARD CORNERS E1/4 CORNER SECTION 24, T3S-R12W AND NE CORNER SECTION 24, T3S-R12W AND EQUIDISTANT BETWEEN A-7 HEREIN RECORDED AND A 1/2" REINFORCING BAR IN A MONUMENT BOX 2.64' NORTH OF A CORNER PREVIOUSLY RECORDED AS A-9 (LCRC LIBER 1, PAGE 487). THE CLOSING CORNER AT A-9 HAS A CONFUSED HISTORY. SEE LCRC FOR A-9 AND FOR M-9, T32-R12W FILED BY THE UNDERSIGNED THIS DATE FOR DETAIL. CORNER LOCATION CHECKS ACCEPTABLY WITH RECOVERED ORIGINAL MONUMENTATION OF SAID PLATS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-7) FOUND 1/2" REBAR IN MONUMENT BOX SOUTH 24.57' FOUND 1/2" REBAR IN MON. BOX AT NE CORNER SECTION 24, T3S-R12W N17W 78.37' SET NAIL AND MICHIGAN DEPT. OF NATURAL RESOURCES TAG IN W. FACE POWER POLE S77E 41.27' SET NAIL AND MDNR TAG IN N. FACE 18" OAK S 16W 138.22' SET NAIL AND MDNR TAG IN E. FACE POWER POLE

(A-8) FOUND 1/2" REBAR SOUTH 48.27' FOUND 1/2" REBAR AT EAST 1/4 CORNER SECTION 24, T3S-R12W S32W 82.16' SET NAIL AND MDNR TAG IN E. FACE 10" CHERRY S51E 44.70' SET NAIL AND MDNR TAG IN N. FACE 6" ELM N66W 32.47' SET NAIL AND MDNR TAG IN SW FACE 12" OAK

Signed by Gary C. Bilow
 For Surveyor's Michigan License No. 26453



2/8/91

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 20, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983