

**SURVEY & REMONUMENTATION**

AUG 06 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo  
(County)  
Portage Twp.

Located In:

Corner Code #

1. Public Land Survey	T <u>3</u> S. R <u>11</u> W.	<u>C-01</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
'96 JUN 7 PM 2 26  
LIBER 2 PAGE 029  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on February 15, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1827: United States Government Surveyors; intersected North boundary 20 lks. East of post. Set post on intersection common to Sections 5 and 6.  
Wh. Oak 8" S. 63° E. 130 lks.  
Wh. Oak 8" S. 07° W. 179 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1955: Hill 'N' Brook Village No. 5, recorded in Liber 21 of Plats on Page 22. Calls for Plat monument and Michigan Brass Cap at Southwest corner of Section 32, T. 2 S., R. 11 W.  
1996: Found Plat monument 13.23' West of State of Michigan Brass Cap at the Southwest corner of Section 32, T. 2 S., R. 11 W.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
5-2-1996

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-01: Northwest corner Section 5, T. 3 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on May 2, 1996, and is accepted as the best available evidence and perpetuation of the corner. Placed 30" Harrison monument in place of plat monument.  
State of Michigan Brass Cap N. 80° W. 13.23'  
PK Nail on South Side of 30" Oak S. 72° E. 33.07'  
PK Nail on Southeast Side of 28" Oak S. 34° W. 11.39'  
PK Nail on South Side of 12" Wild Cherry N. 40° W. 3.13'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 6-6-96