

APR 01 1996

1548

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 NOV 16 PM 3 26

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in City of Portage
Kalamazoo
(County)

Located In: _____ Corner Code # _____

| | | | | | |
|--------------------------------------|---|------------|---|-------------|-------------|
| 1. Public Land Survey | T | <u>3S.</u> | R | <u>11W.</u> | <u>C-11</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

James J. J...
CLERK-REGISTER

LIBER **1 1369**

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
- 6. I.W.M. JOB # 27071

I, Allen H. McMachen, in a field survey on May 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - R. Clark, D.S. Set post
B. Oak 16" S. 46° E. 29 lks.
W. Oak 9" N. 01° E. 29 lks.
- 1960 - Gove Found 2" pipe
6" Tw. Oak S. 10° W. 52.76'
12" Tw. Oak S. 75° E. 66.47'
14" and 6" Tw. Oak N. 25° E. 65.44'
- 1895 - Ed Strong, C.S. Set iron at midway between 1/4 posts E. and W. and at 40.11 1/2 ch. from W 1/4 cor. being same U.S. measure as E. and W. Apple 6" W. 01° N. 1.20, marked no witnesses today.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 6" x 15" Pointed stone with 2" pipe (well point) on South edge of stone. Excavated 3' deep under stone into virgin sand and found nothing. Ed Strong measured (1895) from N. 1/4 cor., Section 32 to N.W. cor., Section 32 at 2647.59' (40.11 1/2), Ingersoll, Watson & McMachen, Inc. measured @ 2648.53', calculated distance from 1960 Gove Assoc. notes = 2650.0'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-15-95

R. E. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Pointed stone is accepted as a careful and faithful re-establishment of the original corner. Removed stone and placed Harrison Monument, Accessories:

- Nail & Tab in East face 20" Twin Oak N. 30° E., 69.70'
- Nail & Tab in Southwest face 24" Oak S. 40° E. 6.04'
- Nail & Tab in West face 10" Twin Oak S. 14° W. 52.81'
- Nail & Tab in Northwest face 14" Oak S. 46° W. 39.05'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 11/10/95