

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo Located In: Corner Code #
Portage Twp. (City)
 1. Public Land Survey T 3S R 11W D-01
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

LIBER

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 1996 OCT 18 AM 11 32
 CLERK - REGISTER
 Register of Deeds Stamp & File Number
 2PAGE 071

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert E. Snell, in a field survey on Feb. 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

This corner not set by original United States Government Surveyors.

1953: Ralph Hansen, R.C.E. #5373; Northeast corner of plat of Hill-N-Brook Village No. 2 recorded in L-19, P-37 of plats, shown as North 1/4 post Section 5, T. 3 S., R. 11 W. and is South 89°-44'-45" East of South 1/4 post, Section 32, T. 2 S., R. 11 W. 14.35' distance.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1954: Ralph Hansen, R.C.E. #5373; recorded plat of Hill-N-Brook Village No. 3, L-20, P-32 of plats shows North 1/4 post Section 5, T. 3 S., R. 11 W., 14.35' East of South 1/4 post, Section 32, T. 2 S., R. 11 W. (tile).

1996: Found plat monument (3" dia. concrete with 1/2" rerod in center) 14.34' East of 3" round tile (South 1/4 post Section 32, T. 2 S., R. 11 W.).

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP 5-2-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-01: South 1/4 post Section 5, T. 3 S., R. 11 W.; ratified by the Kalamazoo County Remonumentation Program Peer Group on May 2, 1996 and is accepted as best available evidence of the position of the corner. This corner not set by original Government Surveyors. Found concrete plat monument 14.34' East of tile set as South 1/4 post Section 32, T. 2 S., R. 11 W. and ratified on May 2, 1996 by Kalamazoo County Remonumentation Program Peer Group. Set 30" Harrison monument in place of plat monument. 6' chain link fence corner is West 3.2' and North 0.75'

Nail in East side	10" W. Cherry	S. 30° E.	30.87'
PK Nail in East side	30" Oak	South	27.64'
Nail/Tab (MSHD) in South side	7" Juniper	N. 88° E.	10.50'
Cross ("x") in Remonumentation Sleeve		N. 80° W.	14.34'

Signed by Robert E. Snell
 Surveyor's Michigan License No. 9734

Date 10/14/96