

**SURVEY & REMONUMENTATION**

SEP 11 1996

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo

(County)

Portage Twp.

Located in:

Corner Code #

- |                                      |                              |                |
|--------------------------------------|------------------------------|----------------|
| 1. Public Land Survey                | T <u>3</u> S. R <u>11</u> W. | <u>E-13</u>    |
|                                      | T _____ R _____              | _____          |
|                                      | T _____ R _____              | _____          |
|                                      | T _____ R _____              | _____          |
| 2. Property Controlling in Section   | S _____ T _____ R _____      | <u>Seq. #2</u> |
|                                      | S _____ T _____ R _____      | <u>pm</u>      |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____      | _____          |
|                                      | S _____ T _____ R _____      | _____          |

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
96 MAR 23 PM 1 47  
Clerk - Register  
*[Signature]*

LIBER 1 PAGE 1500

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

*Sequence #1 is Liber 1 Pg 135D*

I, Robert E. Snell, in a field survey on April 3, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

**A. Description of original monument and accessories and/or subsequent restoration:**

1825: United States Government Surveyors; set post, corner to Sections 32 & 33.

Wh. Oak 14" N. 01° E. 320 lks.  
Wh. Oak 7" N. 42° W. 172 lks.

1889: F. Hodgman, County Surveyor; found stake in marsh, 80 lks. East of corner to Sections 32 & 33. (In remonumentation survey for Schoolcraft corners to Sections 4 & 5).

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1995: Found rusted 3/8" iron in timber in swamp. Further digging revealed wooden stake 1.7' East of iron, top rotted off, old fence post rotted off was found to the North of wood stake. United States Government called for 80 lks. jog. F. Hodgman called for 80 lks. jog, it measured 52.34' from stake to tile set by F. Hodgman, County Surveyor. 3/8" iron is believed to have been used in survey for "Sugarloaf Acres Plat" by Gove recorded in L-22, P-22 of plats.

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
4-18-1996**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-13: Southeast corner Section 32, T. 3 S., R. 11 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on April 18, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found wood stake 52.34' West of 3" round tile set by F. Hodgman in 1889 Remonumentation survey for Schoolcraft Township. Wood stake is believed to be Government stake set in 1825. Removed wood stake and placed 30" Harrison Monument in its place.

PK Nail in West Side	18" Maple	S. 10° W.	51.73'
PK Nail in Northwest Side	Triple 7" Maple	S. 60° W.	38.72'
PK Nail in South Side	12" Maple	N. 50° W.	36.63'
PK Nail in North Side	6" Poplar	S. 44° E.	39.91'

Signed by Robert E. Snell

Date 5-23-96

Surveyor's Michigan License No. 9734