

FEB 03 1999

SECTION

LIBER

2 PAGE 374

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in City of Portage (Twp.)

Table with columns: Kalamazoo (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling In Section, and Miscellaneous Property In Sec.

CLERK - REGISTER

Handwritten signature of the clerk/register.

98 NOV 23 PM 2 57

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Robert E. Snell, in a field survey on Aug. 31, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 9/17/98

Grid table with columns A-M and rows 1-13. A star symbol is placed at the intersection of column H and row 2.

A. Description of original monument and accessories and/or subsequent restoration:

1827: United States Government Surveyors; intersected North boundary 38 lks. East of post. Set post at intersection, corner to Sections 3 & 4.

Burr Oak 14" S. 64 1/2 degrees W. 500 lks.
White Oak 24" S. 05 degrees E. 318 lks.

1874: F. Hodgman, Surveyor; "set stake from Kalamazoo corner and one witness and noted without marking."

White Oak 16" S. 69 degrees W. 96 lks.
Burr Oak 16" N. 47 degrees W. 107 1/2 lks."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1918: Glen C. Wheaton, County Surveyor; Northwest corner Section 3, Portage - stone.
1932: Wilkins & Wheaton Engr. Co.; stone 25.08' East of tile at Kalamazoo corner.
1949: Wilkins & Wheaton Engr. Co.; stone, offset corner for MSHD.
1950: R. Hansen; recorded Kilgore Plat in L-17, P-15 of Plats from tile to Northeast corner Section 3; Portage jog is 25.13'.
1998: During reconstruction of S. Westnedge Ave. found 20"x10"x8" stone with drill mark under bricks in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-01: Northwest corner, Section 3, T. 3 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 17, 1998 and is accepted as a careful and faithful perpetuation of the position of the original closing corner. Found stone placed previous to 1932 8" below surface. Layed stone on its side and placed 20" Harrison monument over stone with monument box over.

PK Nail in East Side Power Pole (in concrete walk) S. 28 degrees E. 36.78'
1" Iron in Monument Box (in concrete walk) S. 72 degrees W. 66.55'
PK Nail in North Side Power Pole N. 40 degrees W. 80.05'
1/2" Iron Back of Walk N. 38 degrees E. 53.95'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 11-20-98