

SURVEY & REMONUMENTATION

AUG 06 1996

LIBER. 2 PAGE 041

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in City of Portage
Kalamazoo
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	3S.	R	11W.	G-12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 96 AUG 1 PM 3 11
 CLERK - REGISTER
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 6. IWM Job No. 29152

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Allen H. McMachen, in a field survey on May 29, 19 96
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - Robert Clark, Jr., Dep. Surveyor
 Set 1/4 Section post
 W. Oak 11 S. 48 1/2° E. 37 lks.
 W. Oak 10 N. 6° W. 74 lks.
- 1873 - Ed Strong, C.S., Stone 17 X 8 X 7,
 found old stake hole from hollow
 in ground where U.S. stood
- ±1970 - Sewer construction removed corner (±10' deep)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" form pin in mon. box.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 6-20-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1" form pin is accepted as the best available evidence of the position of the corner. Replaced 1" form pin with Harrison Monument and mon. box over, Accessories:

- Nail & Tab in U. pole N. 40° W. 42.80'
- 60d nail in 15" Elm N. 30° E. 70.17'
- NW corner of house #10507 S. 55° E. 92.00'
- "PK" Nail in U. pole S. 25° W. 71.07'



Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 8/1/96