

SURVEY &
REMONUMENTATION
MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo Located In: Corner Code #
Texas ^(County) Twp.
1. Public Land Survey T 3S R 12W A-03
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

LIBER

2 PAGE 074

Register of Deeds Stamp & File Number

CLERK - REGISTER
Jessica R. Thompson

96 OCT 18 AM 11 32

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on April 1, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 5-16-1996

A. Description of original monument and accessories and/or subsequent restoration:

1829: United States Government Surveyors; entered west boundary 281 lks. North of post.
Set post at intersection corner to Sections 6 & 7.

W. Oak 9" N. 23° E. 43 lks.
W. Oak 12" S. 70° E. 46 lks.

1869: F. Hodgman, County Surveyor; Section corner (Southwest corner Section 6) stake verified by stumps of both witnesses, marked new witnesses.

Blk. Oak 16" N. 3° W. 59 lks.
Blk. Oak 14" 70 lks. (assumed)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1874: Ed Strong, County Surveyor; Southwest corner (Section 6). Y. Oak 18" N. 3° E. 58 lks. and stone from U.S. stump.

1903: Ed Strong, County Surveyor; Southwest corner found stone 2' below surface on East side of fence 1'.

1914: M. C. Taft, Civil Engineer; found stone from Hodgman witnesses of 1869.

1996: Found stone (10"x6"x12") with drill mark on top down about 1' and 1' East of old fence (downed). Government jog is listed as 281 lks., State of Michigan brass monument 4" dia. is South 190.6'. A 5/8" iron with cap (#10696) S. 60° W. 6.34'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-03: Southwest corner Section 6, T. 3 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on May 16, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found stone with drill mark about 1 foot deep and 1 foot East of old fence line (down) as called for by Ed Strong in a survey in 1874. Placed 30" Harrison monument in place of stone.

| | | | |
|------------------------------|---------------------|-----------|--------|
| Exist. Nail/Tab in West side | 7" Maple | N. 08° E. | 16.70' |
| PK Nail in North side | 28" Oak | N. 70° E. | 31.02' |
| Exist. Nail in South side | 16" Oak | S. 68° E. | 12.07' |
| Exist. Nail in North side | 10" Sassafras | S. 40° E. | 25.67' |
| Exist. PK Nail in West side | RR tie fence corner | N. 06° E. | 34.81' |

Signed by *Robert E. Snell*
Surveyor's Michigan License No 9734

Date 10-14-96

