

7-
2-
APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 NOV 9 AM 8 48

For corners in

Kalamazoo <small>(County)</small>		Located In:	Corner Code #
Texas Twp.		T 3 S R 12 W	B-09
1. Public Land Survey		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

James J. [Signature]
CLERK-REGISTER

LIBER 1 1366
Register of Deeds Stamp & File Number

I, Robert F. Snell, in a field survey on May 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9	30	29	28	27	26	25						
10												
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829: United States Government Survey; Set 1/4 section post.
W. Oak 11" S 1° E 16 lks.
W. Oak 12" N 1/2° E 74 lks.
- 1872: F. Hodgman, County Surveyor; found 1/4 stake from one witness and stump of the other. Planted new stake.
- 1909: E. Strong, County Surveyor; stone W. Oak 9" S 40° E (no dist.)
DBC W. Oak 6" S 70° E 53 lks.
W. Oak 45" S 10° E 31 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1971: Consumers Power Co. P.I. McPherson; set "T" iron on proportionate distance between SE and SW corners and in centerline of blacktop road as occupied.
6" Oak N 10° W 41.70'
30" Oak N 69° E 70.53'
12" Oak S 45° E 65.59'
12" Oak S 05 1/2° W 28.61'
Tel. Pole N 18° E 57.84'
17' ± West of remains of fence to North. Dug for corner in line with fence. Corner as set fits occupation at East 1/8 line.
- 1994: Found "T" iron as set by Consumers Power Co. and used by others. D. Gilchrist L-1, P-247 & I.W.M. L-1, P-753.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
10/20/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-09: South 1/4 post Section 19, T. 3 S., R. 12 W., Ratified by KCRPPG* on October 20, 1994 and is accepted as a careful and faithful re-establishment of the position of the original corner. Found "T" iron as listed in "B" above. Removed "T" iron and placed 20" Harrison Monument with Monument Box in its place.
PK Nail in E. Side Power Pole S 20° E 22.01'
PK Nail in E. Side 10" Oak S 64° W 51.27'
PK Nail in W. Side 8" Oak N 52° W 41.60'
PK Nail in S. Side 38" Oak N 78° E 70.82'

Signed by Robert F. Snell Date 11-6-95

Surveyor's Michigan License No. 9734
* Kalamazoo County Remonumentation Program Peer Group