

MAY 28 1997

COMMISSION

LIBER 2PAGE 097

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Texas Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>12W</u>	<u>C-02</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1996 DEC 11 PM 2 51
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on April 12 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1829: United States Government Surveyors; set 1/4 post.

W. Oak 9" S. 57⁰ E. 4 lks.
W. Oak 10" S. 79^{1/2} W. 25 lks.

1870: F. Hodgman, County Surveyor; found 1/4 Section corner, stake hole from stumps of 2 witnesses. Planted new stake with 4 stones around and marked Hickory 6"
N. 31^{1/2} W. 13^{1/2} lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found remains of stake hole to a depth of 28" with four large stones around. All four stones were larger than 12"x10"x8" found rotted stake on its side on top of stones.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
11-21-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-02: East 1/4 post Section 6, T. 3 S., R. 12 W.; ratified on November 21, 1996 by the Kalamazoo County Remonumentation Program Peer Group and is accepted as a careful and faithful perpetuation of the position of the original corner. Found remains of stake hole with four large stones around as set by F. Hodgman, County Surveyor in a survey in 1870. Placed a 30" Harrison Monument in place of stake hole and left four stones around it.

PK Nail in East Side	20" Oak	South	48.88'
PK Nail in North Side	28" Hickory	West	134.23'
PK Nail in West Side	16" Oak	N. 10 ⁰ E.	58.65'
PK Nail in West Side	Wood Fence Post	N. 75 ⁰ E.	1.98'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-11-96