

**SURVEY & REMONUMENTATION**

AUG 22 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo

(County)

Texas Township

Located In:

Corner Code #

1. Public Land Survey	T 3 S R 12 W	C-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER

1 1276

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
95 MAR 10 PM 3 50

CLERK-REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on May 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1829: U.S. Government Survey; Set Post. Corner to Sections 19, 20, 29 and 30.

- Bl. Oak 12" South 83° West 12 Lks
- Bl. Oak 18" North 63 3/4° East 11 Lks

1878: F. Hodgman, County Surveyor; Found stake hole from remains of one witness. Set stake and stone, marked;

- Wh. Oak 12" South 67 1/2° East 66 1/2 Lks
- Wh. Oak 12" South 60° West 72 Lks

1971: Consumers Power, P.I. McPherson; Southeast corner, Section 19-Found large stone 1' down in approximate line with remains of fence to North, raised with boat spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found boat spike in monument box with a stone 1' below.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
9-15-94 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 Southeast Corner Section 19, T. 3 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994. Found stone 1' below surface as called for in 1878 resurvey by F.Hodgman and is accepted as a careful and faithful perpetuation of the position of the original corner. Lowered stone and placed a 20" Harrison monument and monument box over stone.

Centerline "R" Avenue	North	1.5'
Nail in West Side	Vacant Power Pole	North 50° West 39.74'
PK Nail in West Side	22" Hickory	North 32° East 27.02'
PK Nail in East Side	10" Walnut	South 28° East 42.24'
PK Nail in East Side	24" Oak	South 28° West 36.26'

Signed by Robert E. Snell Surveyor's Michigan License No. 9734

Date 1-17-95