

'95 OCT 19 PM 3 30

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **TEXAS TOWNSHIP**

KALAMAZOO
 (County)

Located In:

Corner Code #

- | | | |
|--------------------------------------|--|-------------|
| 1. Public Land Survey | T <u>3</u> S <u> </u> R <u>12</u> W <u> </u> | <u>C-12</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

James J. Jones
 CLERK-REGISTER

CLERK-REGISTER

LIBER **1 1359**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Allen H. McMachen a field survey on February 2, 1995
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829 - E.H. Lytle, D.S., Set $\frac{1}{4}$ Sec. Post

W. Oak 12" S. $11\frac{1}{2}^\circ$ W. 15 lks.

W. Oak 12" N. 65° E. 21 lks.

1892 - E. Strong, Found Stake, set Stone.

1972 - Smith & Smith, Inc., found pointed Stone with "X" (L. 1, Pg. 114)

Wits:

16" Hickory South 47.2' to Nail

18" Walnut East 15.08' to Nail

16" Walnut North 17.65' to Nail

156.47' North of a Bolt in Paw Paw Lake Road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Pointed Stone with "X" on top.

Matches one of Smith & Smith's

witnesses.

1978 - Acro Engineering, found and used Pointed Stone with "X" L. 1, Pg. 1233, had same Wits. as Smith & Smith, Inc.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 4-20-95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Pointed Stone is accepted as a careful and faithful perpetuation of the position of the original cor. Removed Stone and placed Harrison Monument. Accessories:

Nail & Tab in 15" Walnut North 17.56'

Nail & Tab in 24" Walnut N. 70° E. 14.61'

Nail & Tab in 15" Oak South 56.77'

Nail & Tab in 5" Maple West 12.89'

Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 10/18/95