

**SURVEY & REMONUMENTATION**

FEB 26 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in Texas Township

Kalamazoo

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>3S</u> R <u>12W</u>	<u>D-03</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
97 OCT 22 AM 10 41  
Clerk - Register  
*Annally Johnson*

LIBER 2 PAGE 220

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on April 5, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3		8	9	10	11	12						
4	7											
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

1829: United States Government Surveyors; set 1/4 section post.

W. Oak 5" S. 05 1/2° E. 1 lk.  
W. Oak 7" N. 06 1/2° E. 19 lks.

1910: E. Strong, County Surveyor; stone with cross.

Sassafrass 4" S. 50° W. 49 lks.  
Hickory 3" N. 05° W. 63 lks.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
8-21-1997  
*4.98*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1980: D. Rahilly, RLS #22441; L.C.R.C. L-1, P-856, found stone in monument box 1 foot North of South edge of pavement.

N. 15° W. 32.39' 13" Twin Oak  
N. 37° E. 38.02' Triple Oak  
N. 62° E. 56.04' Twin Oak  
S. 40° E. 33.15' 7" Pine (face)  
N. 45° E. 46.68' 3/8" Re-rod

1996: Found stone in monument box 15" deep, no marks discernable.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-03: South 1/4 post, Section 5, T. 3 S., R. 12 W., Ratified by the KCRPPG on August 21, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found stone in monument box set previous to 1910 survey by E. Strong, County Surveyor. Placed 10" of 20" Harrison Monument in cement over stone in monument box.

(MDOT) Exist. nail/tab in West side	15" Double Oak	N. 12° W.	32.44'
P.K. nail in West side	15" Double Oak	N. 38° E.	37.82'
P.K. nail in East side	12" Oak	N. 58° E.	56.33'
P.K. nail in West side	12" Pine	S. 42° E.	37.14'

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 10-22-97