

# SURVEY & REMONUMENTATION

APR 27 1995

LIBER 1 PG 1154

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> <small>(County)</small>	Located in:	Corner Code #
<u>Texas</u> Township		
1. Public Land Survey	T <u>3S</u> R <u>12W</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
94 JUL 6 AM 11 52  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Thomas W. Chettleburgh in a field survey on March 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner Post set by U.S. Government Deputy Surveyor Thom Whelpley, 1929, 1829  
 Accessories: S58 1/4W Hickory 9" .38, S66W Hickory 6" .29, falling 128 lks (84.48').  
 Ed Strong, 1913, Found stone.  
 Wilkins & Wheaton, 3/8" iron over stone with "X"  
 J. Hunt, 1992, 1/2" iron bar, Recorded LCRC Liber 1, Page 984, Accessories: Stone West 85.63', 18" Oak N65E 42.36', 24" Oak N89W 23.00' Centerline Hydrant S20E 47.30'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Original Corner Post & Accessories not recovered.  
 Found 1/2" iron bar as described and recorded by J. Hunt.  
 Found stone with "X" 1.7' directly below above iron bar.  
 The stone with "X" was accepted as a careful and faithful perpetuation of the position of the original corner and was ratified by the Kalamazoo County Remonumentation Program Peer Group on April 21, 1994.  
 Set 20" Harrison Monument and monument box directly over the stone with "X", (SW Cor. Sec. 33, T2S, R12W West 85.69', Township Line North 0.87')

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 4-21-94 *R.S.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 20" Harrison Monument in monument box.  
 4" Diameter Harrison Monument (SW Cor. Sec. 33, T2S, R12W) N87°W 85.69'  
 Spike S. side 32" Oak N80°W 23.04'  
 Spike NE side 18" Hickory N17°W 68.84'  
 Spike S side Power Pole N86°E 42.90'  
 Centerline Hydrant S35°E 47.25'  
 Centerline N-S road East 4.0'



Signed by Thomas W. Chettleburgh Date July 5, 1994  
 Surveyor's Michigan License No. 16036