

NOV 25 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Texas Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 3S R 12W	E-04
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 98 OCT 22 AM 11 37
 Clerk - REGISTER
Jessie Johnson

LIBER 2 PAGE 355
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8	●	9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert E. Snell, in a field survey on May 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 5-21-1998
RES

- A. Description of original monument and accessories and/or subsequent restoration:
- 1829: United States Government Surveyors; set 1/4 post.
 W. Oak 6" S. 87° W. 53 lks.
 W. Oak 12" N. 16 3/4° E. 63 lks.
 - 1869: F. Hodgman, County Surveyor; "Found old stake and brick around. Partly washed out in a gully by water. Drove a new stake and marked.
 Hickory 10" N. 46° W. .78 chains Y. Oak 4" S. 12° E. .74 chains"
 - 1910: E. Strong, County Surveyor; stone, brick and large post.
 Y. Oak 6" S. 15° W. .38 chains
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1947: Wilkins & Wheaton Engr. Co.; found stone and brick.
 Double Oak Northeast 73.6'
 Oak S. 20° W. 31.1'
 B. Oak N. 20° W. 103.55'
 - 1962: Michigan Department of Transportation; 1" pipe over stone.
 - 1998: Found 1" pipe x 2.3' in monument box with cap #22441 inside. Found large stone (1.5' x 1/2' x .65') 2.0 feet below surface with large piece of brick on south side, 0.18' East and 0.03' South of 1" iron pipe.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- E-04: East 1/4 post, Section 8, T. 3 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on May 21, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found large stone and brick as set by E. Strong, County Surveyor in 1910 survey. Placed 20" Harrison monument over stone with monument box over.
 PK Nail in East Side Double Oak N. 30° E. 74.32'
 Exist. Nail/Tab in West Side Oak S. 55° E. 62.45'
 Exist. Nail/Tab in East Side Oak S. 20° E. 54.44'
 PK Nail in North Side Power Side S. 60° W. 86.26'

Signed by *Robert E. Snell* Date 10-22-98
 Surveyor's Michigan License No. 9734