

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 08 2000

For corners in Texas Twp.

Kalamazoo Located in: Corner Code #
(County)

1. Public Land Survey T 3 S R 12 W E-07
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

SECTION



Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on June 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829: United States Government Surveyors, E. H. Lythe; set post, corner to Sections 16, 17, 20 & 21.
White Oak 18" N. 35° E. 68 lks.
Black Oak 10" S. 81° W. 79 lks.
- 1872: S. Hodgman, Deputy County Surveyor; found stake hole from 1 witness - standing alone.
- 1893: E. Strong, County Surveyor; stone gone. Ran from South 1/4 (16) over 1/8 post West and doubled line. Set stone for SWC.
Yellow Oak 7" Northeast 40 lks.
Yellow Oak 7" Southeast 41 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1948: Wilkins & Wheaton Engr. Co.; found stone, drilled.
- 1949: Wilkins & Wheaton Engr. Co.; placed monument.
- 1999: Found 1/2" x 10" iron in 5" steel sleeve just below surface of road. 20" below road surface found plat monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-07: Southwest corner, Section 16, T. 3 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 9, 1999 and is accepted as the best available evidence of the position of the original corner. Found plat monument (1/2" iron in concrete) under 1/2" x 10" iron. Plat monument was placed in 1949 by Wilkins & Wheaton Engr. Co. in place of drilled stone set by E. Strong, County Surveyor in 1893 survey. Placed 20" Harrison monument in monument box over plat monument.

Nail/Tab in West Side	Fence Post	N. 03- E.	31.05'
Nail/Tab in South Side	18" Oak	N. 62- E.	45.29'
Nail/Tab in West Side	Power Pole	S. 18- W.	63.00'
Nail/Tab in West Side	14" Oak	N. 50- W.	61.22'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 11-15-99

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-9-1999