

'95 OCT 19 PM 3 30

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in TEXAS TOWNSHIP Located In: Corner Code #  
KALAMAZOO (County)

*James J. Jones*  
 CLERK-REGISTER

- |                                      |                                   |             |
|--------------------------------------|-----------------------------------|-------------|
| 1. Public Land Survey                | T <u>3</u> S <u>R</u> <u>12</u> W | <u>E-11</u> |
|                                      | T ___ R ___                       | _____       |
|                                      | T ___ R ___                       | _____       |
|                                      | T ___ R ___                       | _____       |
| 2. Property Controlling in Section   | S ___ T ___ R ___                 | _____       |
|                                      | S ___ T ___ R ___                 | _____       |
| 3. Miscellaneous Property in Section | S ___ T ___ R ___                 | _____       |
|                                      | S ___ T ___ R ___                 | _____       |

LIBER **1 1357**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Allen H. McMachen field survey on December 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1829 - U.S. Government, set Post.  
 Wh. Oak 16" S. 19° W. 11 lks.  
 Wh. Oak 8" S. 85° E. 10 lks.
- 1885 - E. Strong, found old stake hole Stone stake, Plow Point.  
 B. Oak 10" S. 34° E. 76 lks.
- 1972 - Dennis Middleton, found 3/4" Iron Bar over 3/4" Iron Bar.  
 10" Oak South 41.22' to Nail  
 10" Sassafras N. 20° W. 42.37' to Nail.  
 2' South of centerline E. & W. Road.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- Found 3/4" Iron in Mon. Box, removed Box and Iron and found second 3/4" Iron directly below. Found Irons 3' S. of centerline and fit 1972 witnesses (no Nails found).
- 1972 - John Kester, found Iron in Mon. Box fence cor. North 31.8'  
 7" Catalpa S. 05° E. 32.0'  
 3' S. of centerline "S" Ave.
- 1971 - Wilkins & Wheaton  
 Iron  
 14" Maple N. 60° E. 155.0' to Face.  
 TW. 24" Maple S. 40° E. 113.4' to Face.  
 Fence cor. North 3.5'

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 4-20-95 *[Signature]*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Found Iron Rod is accepted as a careful and faithful re-establishment of the position of the original cor. Removed Irons and placed Harrison Monument and Mon. Box over. Accessories:  
 Nail & Tab in S.W. Face 14" Walnut N. 25° W. 42.10'  
 Nail & Tab in S.E. Face 12" Triple Walnut N. 30° E. 30.74'  
 Nail & Tab in N. Face 12" Mulberry S. 70° E. 82.15'  
 Nail & Tab in W. Face 26" Oak South 40.55'



Signed by Allen H. McMachen  
 Surveyor's Michigan License No. 16935

Date 10/18/95