

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '95 OCT 19 PM 3 30

COMMISSION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in TEXAS TOWNSHIP
KALAMAZOO Located In: Corner Code #
 (County)

- | | | |
|--------------------------------------|------------------------------|-------------|
| 1. Public Land Survey | T <u>3</u> S. R <u>12</u> W. | <u>E-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

James H. Young
 CLERK-REGISTER

LIBER **1 1358**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Allen H. McMachen a field survey on December 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1829 - E.H. Lytle, D.S., Set $\frac{1}{4}$ Sec. Post
 R. Oak 10" S. 02° W. 17 lks.
 W. Oak 30" N. 89° W. 11 lks.
 - 1878 - F. Hodgman, Found Stake from remains of 2 Wits., set Stone with "X"
 - 1885 & 1892 - E. Strong, found Stone.
 - 1948 - Wilkins & Wheaton, set Iron Rod at $E\frac{1}{4}$ cor. ($W\frac{1}{4}$ cor., Sec. 33) by doubling up from found $\frac{1}{8}$ corner and $C\frac{1}{4}$ cor. of Sec.. 33.
 - 1972 - John Kester, found Iron Rod.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found $\frac{1}{2}$ " Iron Rod set by Wilkins & Wheaton in 1948.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 4-20-95 *R.S.*



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Found $\frac{1}{2}$ " Iron Rod is accepted as a careful and faithful reestablishment of the position of the orig. cor. Removed Iron and placed Harrison Mon.,
- Accessories:
- Nail & Tab in 6" Oak N. 05° W. 16.40'
 - Nail & Tab in 16" Oak N. 80° W. 21.94'
 - Nail & Tab in 12" Oak S. 70° E. 27.78'
 - Nail & Tab in 10", 6" & 6" Triple Stemmed Oak S. 30° W. 51.35'

Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 10/18/95